


Quality of Service Performance Results for July-September 2013

Nation-wide Outdoor Service Coverage

This indicator measures Nation-Wide Outdoor Service Coverage for the 3G cellular network. Service coverage is determined by signal strength. The availability of service coverage is the ability of a cellular network to achieve the minimum signal strength of at least -100dBm. Under IDA's 3G Public Cellular Mobile Telephone Service ("**PCMTS**") QoS framework, mobile operators are required to achieve Nation-Wide Outdoor Service Coverage of >99%. In order to better measure the end users' experience*, IDA has used mobile handsets to collect the signal strength sample readings for all service coverage indicators starting from Q2 2013.



*Based on IDA's coverage performance surveys which included nation-wide outdoor drive test and areas such as housing estates/town centres, outdoor recreational areas and above ground MRT tracks.


Note: End users' individual experience may differ due to various reasons such as model of handset used, handset settings, number of users in the vicinity, etc.

Call Success Rate

This indicator measures the percentage of successful call attempts made on the 3G cellular network. A call attempt is deemed successful when the calling party (the individual who makes the call) gets connected to the called party (the individual who receives the call) or receives a busy tone. Under IDA's 3G




PCMTS QoS framework, the mobile operators are required to achieve >99% success rate (average across all cell localities during busy hour).



Note: Call success rates are based on the mobile telecommunication operator's actual network traffic logs.

Call Drop Rate

This indicator measures the percentage of unintended disconnection of 3G mobile calls by the cellular network during a 100 second call. Under IDA's 3G PCMTS QoS framework, mobile operators are required to achieve <1% drop call rate (average across the entire month).



Note: Call drop rates are based on the mobile telecommunication operator's actual network traffic logs.



In-Building Service Coverage

This indicator measures in-building service coverage for the 3G cellular network. Under IDA's 3G PCMTS QoS framework, mobile operators are required to achieve a service coverage of >85% per building. Service coverage is measured at randomly selected buildings and at publicly accessible areas within the tested buildings as a proxy for the coverage in the entire building to avoid disturbing residents. For buildings that have failed IDA's compliance standard, mobile operators will have a period of six months to improve the coverage within the buildings. IDA will audit the buildings again after the sixmonth period.

IDA's Performance Survey Period: Q3 2013

M1	SingTel Mobile	StarHub Mobile		
No of buildings passed/No of buildings tested Compliance standard >85% per building				
60/60*/**	60/60*	60/60*		
(retest results, original test result in Q3 2013 was 46/60)	(retest results, original test result in Q3 2013 was 59/60)	(retest results, the original test result in Q3 2013 was 59/60)		

^{*} The updated performance survey results after the six-month rectification period

Note: The same sixty buildings were tested across the three mobile operators. The performance of each of the MTO varies for each of the building tested. End users' individual experience may differ due to various reasons such as model of handset used, handset settings, building/unit structures, number of users in the vicinity, etc. The in-building service coverage results are based on IDA's coverage performance surveys.

Tunnel Service Coverage

This indicator measures service coverage for the 3G cellular network within tunnels. Under IDA's 3G PCMTS QoS framework, mobile operators are required to achieve a service coverage of >95% for existing road and MRT tunnels.*

IDA's Performance Survey Period: Q3 2013

	M1	SingTel Mobile	StarHub Mobile
Compliance standard: >95% for existing road and MRT tunnels			

^{**} IDA had previously postponed the retest at one of the buildings till November 2014 as M1 had encountered delays beyond its reasonable control in enhancing mobile coverage at the building. IDA has completed the retest at the building and the result has been updated accordingly



М1	SingTel Mobile	StarHub Mobile		
Central Expressway (Roa	al Expressway (Road Tunnel)			
Pass	Pass	Pass		
Kallang-Paya Lebar Expr	allang-Paya Lebar Expressway (Road Tunnel)			
Pass	Pass	Pass		
Fort Canning Tunnel (Ro	ort Canning Tunnel (Road Tunnel)			
Pass	Pass	Pass		
Woodsville Tunnel (Road	odsville Tunnel (Road Tunnel)			
Pass	Pass	Pass		
North South Line (MRT)	North South Line (MRT Tunnel)			
Pass	Pass	Pass		
East West Line (MRT Tun	: West Line (MRT Tunnel)			
Pass	Pass	Pass		
Circle Line (MRT Tunnel)	cle Line (MRT Tunnel)			
Pass	Pass	Pass		
North East Line (MRT Tui	lorth East Line (MRT Tunnel)			
Pass	Pass	Pass		

^{*}For new tunnels where deployment work was committed by mobile operators after 26 January 2012, a higher standard of >99% applies.

Note: End users' individual experience may differ due to various reasons such as model of handset used, handset settings, number of users in the vicinity, etc. The tunnel service coverage results are based on IDA's coverage performance surveys.